ADDENDUM No. 2
Request for Competitive Sealed Proposals (CSP)
20CSP079 HVAC and Civil Improvements at Cook Elementary School

November 15, 2019

Received by bidder:

Date:_____

Name:_____

Signature:_____

Item 1: Abatement Specifications and Updated Drawings

The drawings for 20CSP079 (19-0016-COOK) have been updated and are available at Miller IDS under 20CSP079.

Owner

AUSTIN INDEPENDENT SCHOOL DISTRICT
Mr. Rumman Zamir
4000 S. IH 35 Frontage Road
Austin, Texas 78704

BURCHAM ENVIRONMENTAL SERVICES, L.L.C.
P.O. Box 2496

Section 100 - Scope of Work - Asbestos Abatement

RELATED DOCUMENTS:

This specification covers the abatement of asbestos hazards from building structures and components listed in these Contract Documents. It is the intent of the Contract Documents to show all of the work necessary to complete the project.

All work is to be completed following these specifications and all applicable Federal, State and local rules and regulations.

100.2.7 Cover floor areas, except where floor tile and/or mastic materials are to be removed, with two layers of 6-mil plastic sheeting, individually applied, extending at least 12 inches up the walls. Cover wall areas, except those surfaces scheduled for demolition/renovation, with two layers of 4-mil plastic sheeting, individually applied, extending at least 12 inches onto the floor. Seal seams to prevent leakage. No seams shall be located at wall to wall or wall to floor joints. Do not cover contaminated surfaces.

100.2.8 Place work areas under reduced air pressure as specified. Allow no air movement system or air filtering equipment to discharge unfiltered air outside the work area. Submit proposed number, rated flow, placement and route of exhaust to Project Manager for review and approval prior to beginning work. The Consultant may complete this process and provide to the Contractor.

100.2.9 Ensure that all barriers and plastic sheeting enclosures remain effectively sealed and taped for the duration of abatement and subsequent cleaning. Visually inspect enclosures at the beginning and end of each work shift. Repair damaged barriers and remedy defects immediately upon discovery. Use smoke methods or other approved methods to test effectiveness of barriers when requested by the Project Manager.

100.2.10 Maintain a sign-in/out log in the immediate area of the change room to be signed by every person each time upon entering and leaving the work area(s).

100.2.11 Inside each work area place a fire extinguisher with a minimum NFPA rating of 10BC (dry chemical) for every 3,000 square feet, or fraction thereof, of work area for the duration of abatement and subsequent cleaning activities. The same type of fire extinguisher is to be placed in the vicinity of the change room.

100.2.12 Contractor is to install a fully functional 3-stage decontamination facility (to include two separate airlocks) at the entrance to the containment area, and warm water is to be available at the shower

opening and at the decontamination facility.

Section 100.4-Removal Activities (Floor Tile and/or Mastic)

100.4.1 Prepare work area as previously specified.

100.4.2 Thoroughly wet the asbestos-containing materials to be removed with amended water prior to handling or stripping to reduce fiber dispersal into the air. Accomplish wetting with a fine mist of

Section 100.10-Approved Project Managers

100.10.1 The Asbestos Consultant for this project (Kent Burcham, License # 10-5317) authorizes the following Project Managers to perform visual inspections per TAHPA Rule 295.58 (i)(B); Chris Beltran, Angel Benson, Sage Alexander, Yesmisi Adetomi604Inr,

200.14 The work area is to be restricted only to authorized, trained, and protected personnel. These may include the Contractors employees, employees of the Subcontractors, Owner employees and representatives, Federal, State and Local inspectors and any other appropriate individuals. The Contractor shall designate his certified project supervisor as the only person, other than representatives of Burcham Environmental Services, L.L.C., and the Owner, who can allow or deny the entrance of all other persons into the work area. Texas Department of State Health

Damaged, deteriorating or previously used dirty materials as determined by Burcham Environmental Services, L.L.C., shall not be used and shall be properly removed from the work site.

200.19 A meeting with the Contractor will be held at least weekly to determine work progress and compliance with State, Federal and local requirements, these plans and specifications, and any other governing regulations.

200.20 Definitions:

Abatement: Procedures to control fiber release from asbestos-containing materials. Includes removal, encapsulation, enclosures, repair, demolition and renovation activities.

Accredited or Accreditation: When referring to a person or a laboratory means that such a person or laboratory has met the training, experience, and/or quality control requirements to perform work in accordance with AHERA.

Adequately Wet: Means sufficiently mix or penetrate with liquid to prevent release of particulates. If visible emissions are observed coming from asbestos-containing material, then that material has not been adequately wetted. However, the absence of visible emissions is not sufficient evidence of being adequately wet.

AHERA: Means the Asbestos Hazard Emergency Response Act of 1986 (PL99-519) and rules and regulations enacted by EPA for its implementation.

AHERA Abatement Project Designer: Means a person who develops plans and specifications for the abatement of asbestos. For the purposes of these rules, Abatement Project Designers will be considered to be a category of contractors.

Airlock: A system for permitting ingress and egress with minimum air movement between a contaminated area and an uncontaminated area, typically consisting of two curtained doorways separated by a distance of at least three feet (3') such that one passes through one doorway into the airlock, allowing the doorway sheeting to overlap and close off the opening before proceeding through the second doorway, thereby preventing flow-through contamination. Each curtain will be constructed of at least 3 layers of polyethylene or polyvinylchloride a minimum of 6-mil thickness. The first sheet will be attached along the top of the doorway, and along one side of the doorway. Each subsequent layer of sheeting will be attached along the top of the doorway and along the opposite side-2.8 (e)-2.7 (t5.2 (h)17.8 (t9j -0.001 Tc -1.2Tw -35.410 Td [(p)-7 (o)-7a2.9 (h)8 (r)-2.

cummingtonite-

HVAC: Heating, Ventilation and Air Conditioning system.

Loadout: See Waste Transfer Airlock.

Lockdown: Lockdown is the procedure of applying a protective coating or sealant to a surface from which asbestos-containing material has been removed. Its primary function is to control and minimize the amount of airborne asbestos fiber generation that might result from any residual asbestos-containing debris on the substrate. Though the substrate may appear to be clean, minuscule fibers may have become lodged in cracks or crevices that were inaccessible.

Movable Object: A piece of equipment or furniture in the work area which can be removed from the work area.

NESHAP: The National Emission Standard for Hazardous Air Pollutants (40 CFR Part 61).

NIOSH: The National Institute for Occupational Safety and Health
Building J NE - Room 3007
Atlanta, Georgia 30333

On-Site Day: Any day on which work is being done on an asbestos abatement project that would require the services of a licensed asbestos worker, including but not limited to site preparation, establishment of decontamination facilities, removal and encapsulation, lock-down, r

capability be utilized, or be located at the jobsite.

300.1.10

TECHNICAL REQUIREMENTS

ADDENDUM TWO

HVAC & Civil Improvements at Cook ES

AISD Cook Elementary School Renovations Bid Set dated October 15, 2019.

DRAWINGS

Mechanical

Sheet M101 ð (Re-Issued)

2401 Saner Rd. Bldg. 55, Suite 210 ♦ Austin, Texas 78741 ♦ Main: 512.445.2090 ♦ Fax: 512.445.2099 ♦ www.guer