

requirements of local jurisdiction. Burger Stadium is located within the Edwards Aquifer Recharge Zone. All construction activities within this recharge zone are regulated by the Texas Commission on Environmental Quality (TCEQ). This project is no exception. All work activities that produce runoff from the site that have the potential to pollute the receiving storm water collection systems that ultimately feed into the Edwards Aquifer shall be in full compliance with current TCEQ rules and regulations. Please contact TCEQ directly for any specific requirements or questions regarding the particular scope of work for this project. See Addendum No. 1, dated 12.03.19

6. Request the Note for Expansion Joint be added to Drawing S2.07 and S2.08. Request that the Expansion Joint Width be provided in an Anticipated Movement with a Maximum / Minimum Width so that we can make sure to price a Expansion Joint Size appropriate for this installation.
ANSWER: Contractor to provide bid for both a 1" and a 2" wide expansion joint. See revised drawings (addendum #1, dated 12.03.19).

7. Request that AISD and JQ Engineering allow contractors the Option to bid Asphalt Paving or Concrete Pavement at these locations.
ANSWER: Request that AISD and JQ Engineering allow contractors the Option to bid Asphalt Paving or Concrete Pavement at these locations.

8. Request AISD to check with their Purchasing Department to see if they can find the Original Bleacher Plank Manufactures contact information.
ANSWER: JQI and Owner are unable to locate original product data on bleachers.

9. Sheet S.201 S.204 shows asphalt paving repairs and does not include dimensions or quantities. Can quantities be provided to ensure contractors are bidding apples to apples?
ANSWER: Sheet S.201 S.204 shows asphalt paving repairs and does not include dimensions or quantities. Can quantities be provided to ensure contractors are bidding apples to apples?

10. Plan notes #1 states for contractor to survey the stadium for deteriorated/delaminated areas. Can clarification be provided for required extent of survey? Ex. Are we surveying only the areas adjacent to identified repairs? Or do we need to allocate time to survey the entire stadium and quantify repairs based on survived data?
ANSWER: The contractor is to survey areas adjacent to identified repairs only.

11. Will painting or color matching be required? Or will a standard concrete finish be sufficient?
ANSWER: Painting or color matching is not required.

12. construction. Can you provide more detail on when they would be required?
ANSWER: Covered walkways to restrooms would be required when construction activities are taking place over pathways to restrooms.

13. Plan notes #10 state to power wash the topside of the superstructure and walls after construction is complete. Can you provide a specification for power washing?

ANSWER: Notes clarifying power washing requirements have been added to the drawings. See addendum #1, dated 12.03.19