



Q: What is the wind rider for this project?

A: Specification Section 075419 Polyvinyl-Chloride (PVC) Roofing, 1.10, B, 1., states "Wind Rider: warranty to include wind speed rider coverages up to 90 mph."

Q: Will new wall panels cover existing windows on area A6?

A: Yes, a new wall with metal wall panels are to be installed to cover the windows on Area A-6 as shown in Detail 1/R3.01.

Q: Was this projects site-visit a mandatory Site-Walk? Will contractor still be able to bid if they did not attend?

A: Project site visit was not mandatory and Contractors that did not attend the site walk may submit Bids in accordance with the Project Documents.

Q: Project Roof Drawings. Page R3.00 Details 1A and 1B state that Insulation is to be 2





4000 S IH 35 Frontage Road, Austin Texas, 78704, 4<sup>th</sup>

